



026-2016

LETTER TO COMMISSION

TO: Mayor Philip Levine and Members of the City Commission

FROM: Jimmy Morales, City Manager

DATE: January 20, 2016

SUBJECT: **54" SANITARY SEWER REDUNDENT FORCE MAIN - CONSTRUCTION UPDATE**

CONSTRUCTION UPDATE

The contractor accepted delivery of a 54" pipe on Wednesday January 20, 2016. The pipe will be installed at 11th Street, between Euclid Avenue and Espanola Way. Once the pipe is installed, the contractor will be welding the sections together. Assembly of these sections will require the cross streets on 12th, 13th, and 14th to be blocked from through traffic. During this entire operation, Euclid Avenue will be open for local traffic only. Parking along both sides of the street will be maintained. Construction detour signs will be placed accordingly.

Directional drilling of the 12" diameter pilot borehole commenced today and should be completed by Wednesday, January 27, weather permitting. The normal boring operation is between 8AM and 6PM. The most significant impact to residents will be noise associated with the drilling equipment. After the pilot bore-hole alignment is approved, the contractor will enlarge the bore hole diameter to 72 inches. This work is scheduled to start the week of January 25th and continue for approximately four weeks. The drilling equipment will be moved to 3rd Street sometime during these four weeks.

The Department of Public Works, Transportation Department and the Parking Department are working closely with the contractor to minimize the traffic and parking interruptions.

JLM/ETC/SJF/BAM/WRB/IAV